

## BS 5975:2019

Table 2 – Categories of Design Check in Temporary Works

Category	Scope	Comment	Independence of Checker
0	Restricted to standard solutions only, to ensure the site conditions do not conflict with the scope or limitations of the chosen standard solution. These may include standard trench boxes.	This applies to the use of standard solutions and <b>not</b> the original design, which requires both structural calculation and checking to Category 1,2 or 3, as appropriate.	Because this is a site issue, the check may be carried out by another member of the site or design team.
1	For simple designs. These may include: formwork; falsework; needling and propping to brickwork openings in single storey construction.	Such designs would be undertaken using simple methods of analysis and be in accordance with the relevant standards, supplier's technical literature or other reference publications.	The check may be carried out by another member of the design team.
2	On more complex or involved designs. Designs for excavations including excavation support using sheet piles, for foundations, for structural steelwork connections, for reinforced concrete. Designs where stability is obtained by restraint at the top of the temporary works (e.g. top restrained falsework).	Category 2 checks would include designs where a considerable degree of interpretation of loading of soils' information is required before the design of the foundation or excavation support or slope is carried out.	The check should be carried out by an individual not involved in the design and not consulted by the designer.
3	For complex or innovative designs, which result in complex sequences of moving and/or construction of either the temporary works or permanent works. It also includes basement excavations and tunnels.	These designs include unusual designs or where significant departures from standards, novel methods of analysis or considerable exercise of engineering judgement are involved.	The check should be carried out by another organization and should include an overall check to assure co-ordination of the whole design.